

Preliminary Design Report

TO: PHEASANT RUMP NAKOTA NATION

ATTN: DARREN SVEDAHL, PHEASANT RUMP NAKOTA NATION

PROJECT: #2782

DATE: 17 AUGUST 2021

RE: PRELIMINARY DESIGN FOR THE PHEASANT RUMP NAKOTA NATION

WASTE TRANSFER STATION

PURPOSE OF THE PRELIMINARY DESIGN AGREEMENT

The following information is provided to establish the design guidelines to be used in the design and specifications for the new Pheasant Rump Nakota Nation (PRNN) Waste Transfer Station. Following approval from PRNN and Indigenous Services Canada (ISC) of this preliminary design any changes to the final design guidelines will have to be addressed with proper change orders reflecting impact to both price and schedule. The function of this preliminary design report and the above process is to help both parties remember what is and is not included in the design of this transfer station within the scope of this project.

PROJECT DESCRIPTION

PINTER & Associates Ltd. (PINTER) has been retained by PRNN to provide engineering services for design and construction of a Pheasant Rump Nakota Nation Transfer Station. Transfer stations offer a range of benefits. Consolidating waste from multiple collection vehicles and agencies at an established transfer station—then hauling it via large transport containers—is more economical than hauling the waste directly to a landfill truck by truck. Transfer stations let solid waste managers screen loads, separate recyclables, and ensure that no hazardous waste or other undesirable materials enter the waste stream.

A transfer station is far more than a simple shed where waste gets dumped for a few hours before a trailer or rail car carries it away. There are several things a solid waste manager should keep in mind to ensure that their facility runs as efficiently as possible to best serve the community.

The objectives of this project and preliminary design to be met include:

- 1. A new solid waste transfer station that better meets your community's needs.
- 2. Provide a secure facility difficult to vandalize.
- 3. Provide a simple, safe, and effective facility for the transfer of waste.
- 4. Utilize on-site First Nation personnel as an integral part of the team for the design, construction, and operation of the facility.

710A 48th Street East
Saskatoon, SK S7K 5B4
Treaty 6 Territory, Canada email: pintermain@pinter.ca

The deliverables for this project include the pre-design, design, review, tender, construction, construction quality assurance/quality control (QA/QC), as built reporting for a new solid waste transfer station, and post-construction services.

Specific deliverables and components for this pre-design include drawings and descriptions of the following:

- Layout based on current and future needs
- Retaining walls
- Roads
- Guardrails
- Recycling areas
- Security
- Bins
- Equipment Recommendations
- Shelter(s)
- Cost estimate (Class C) to Construct

The following sections present the design criteria and preliminary design for this project.

TRANSFER STATION PRELIMINARY DESIGN

The following transfer station design has been prepared in accordance with the PWC/ISC Technical services standards for drawings, ISC AutoCAD standard manual, and the ISC Design Guidance for Small Scale Transfer Stations Manual. The guidelines consider best engineering and industry practices, correspondence with Pheasant Rump Nakota Nation, observations made during site visits to the existing temporary Pheasant Rump Nakota Nation Transfer Station and potential construction locations for the new transfer station, a review of the PRNN Solid Waste Management Feasibility (SWMF) Study, and a review of other relevant anecdotal information. The conceptual design has been developed using information gathered on the site through a geotechnical investigation and topographical survey.

Facility Size and Location

- The transfer station is to be sited on legal land location NW-19-08-05W2M.
- The proposed site extents are approximately 110 metres (m) by 130 m. These extents do not include the right of way or Highway 605 west of the Site or the grid road located north of the Site.
- The transfer station is designed based on population data and projections from the 2019 PRNN Solid Waste Management Feasibility Study (SWMFS). It will be sized for the projected 2046 (25 year) on reserve population of 222 people at an expected 1.77% population growth rate. The year 2046 was not listed in the SWMF Study; however, using the methodology from the SWMF Study, the 2046 on-reserve population is projected to be 222.

- The Pheasant Rump Transfer Station shall be open 2 to 4 days per week and an attendant will be on site during operating hours.
- Using the methodology presented in the SWMF Study, the stated waste generation assumption of 2.0 kilograms per person per day (without diversion) would indicate a total solid waste generation of approximately 2.5 tonnes/week by 2046.
- Waste from the transfer station will be picked up once per week and hauled by a contracted hauler to the Redcoat Waste Resource Authority (RWRA) Landfill, located approximately 56 kilometers(km) north of Pheasant Rump near Kipling, Saskatchewan (SK). The distance hauled in a single round-trip to the RWRA Landfill is approximately 112 km.
- The proposed transfer station facility is to be located within Pheasant Rump Nakota Nation lands, approximately 600 m north from the community centre to aid in preventing vandalism and trespassing.
- The facility is at least 300 m from any schools, hospitals, food establishments, or residences. Siting considers municipal zoning bylaws and local bylaws.
- Site size includes space for transfer buildings, waste and recycling diversion, composting, and the capability to expand for further diversion development and 25-year population growth projections.
- Sufficient space for on-site roads to allow for efficient vehicle routing, queuing of collection vehicles, and parking for trailers and site staff are incorporated.

General Site Layout

- A geotechnical investigation and topographical survey of the site assisted in the development of site extents and a site layout. It would be beneficial to utilize natural topography to aid in the construction of ramps, elevated platforms, etc.; however, the area to be used for the proposed transfer station is relatively flat, with slight relief to the east.
- Geotechnical considerations are used to assess building and retaining wall structure support. The preliminary design has been finalized based on the data collected during the geotechnical investigation and topographical survey.
- The general site layout consists of a gated entrance, an attendant shack, access roads, a grade separated bin area for domestic waste, a similar area for recyclables, white metals and oversized items, a tire storage area, hazardous waste material storage area, and security fencing and lighting.
- Active areas such as the tip area, storage areas, etc. will be at least 5 m from all property lines.

Road Design and Site Access

- For adequate site access, the facility will require access roads and ramps.
- Roads will have all weather surfaces.
- Two-way traffic roads will be at least 7.0 m in width (not including shoulders) and one-way traffic roads will be at least 6 m.
- All roads will feature a 20 m minimum turning radius.
- Ditches will be incorporated into the overall site drainage system.
- The area in front of the bin area will have sufficient room for turning and backing up large vehicles.
- There will be room for queuing on site.

Attendant Shack Design

- An attendant shack will be located on the north site near the gate.
- The building will be approximately 2.4 m wide and 2.4 m long.
- There will be windows facing the site entrance, the MSW bins area and the south of the transfer station.
- The building will have access to power for heating in winter and other basic conveniences.

Bin Area (Municipal Solid Waste)

- The bin area is located in the north portion of the site.
- The current preliminary design allows for four 6-yd bins.
- The bins will act as a direct dump location and will be hauled off site when at capacity.
- The design will allow for roll off bin sizes that are up to 1.8 m long by 1.5 m wide (6-yd bins).
- The direct dump platform will be elevated near the top of bins.
- A retaining wall will be installed along the front of the bins.
- There will be a bumper railing along the top of the retaining wall to protect the retaining wall and roll-off bin.
- The bins will sit on a lower lay down area that will be accessible via transport trucks.
- Signage will be posted at each bin to ensure the proper materials are disposed of in the proper location.

- Along the western edge of the site is a shed for temporary disposal of household hazardous wastes. This area will include a concrete containment pad with a small roll off bin for batteries, a canopy or small structure for paint cans and materials, and an area for used oil disposal in a double walled tank
- The household hazardous waste drop-off facility will be designed in accordance Saskatchewan and ISC Hazardous Materials Storage guidance. It will include an impermeable base, secondary containment, security, prominent identification, and emergency response equipment.
- Should the household hazardous waste facility store waste for a continuous period of more than 365 days, or if more than 10 tonnes is stored at any time, approval is required.

Roll Off Bin Area (Oversize and Recyclables)

- The recyclable roll-off bin area is located in the south portion of the site and is approximately 20 m by 15 m in total size.
- The current preliminary design allows for one roll off bin for oversized items.
- The design will allow for two 6-yd bin sizes that are up to 1.8 m long by 1.5 m wide (6-yd bins).
- The direct dump platform will be elevated near the top of bins.
- A retaining wall will be installed along the front of the bins.
- There will be a bumper railing along the top of the retaining wall to protect the retaining wall and roll-off bin.
- The bins will sit on a lower lay down area that will be accessible via transport trucks.
- Signage will be posted at each bin to ensure the proper materials are disposed of in the proper location.
- These bins would be used for segregated recyclable materials and any oversized items.
- Segregated materials designated for each roll off bin will be discussed with the Client. Potential materials include:
 - Paper and cardboard
 - Plastics
 - Tires
 - White metal
 - Glass
 - Scrap metals
 - Furniture

Utilities

- The transfer station attendance shack and site lighting will require power.
- Security cameras and lightening will be installed on-site.
- It may be possible to run power from the line supplying the oil and gas wells located on the property directly adjacent to the north of the site. The power could be run to a transformer near the attendance shack building on the eastside of the site. Single phase power could be run underground, across to the site to the attendant shack.
- Options for power will be discussed with the Client throughout the draft design stage.

Site Security

- The site will be enclosed by a 6 to 8-foot perimeter fence using chain link topped with barbed wire.
- At the gate, there will be a camera to monitor the premises.
- The site will have proper lighting in place to increase visibility
- The site will have an entrance sign with site name, emergency contact numbers, a list of prohibited wastes, tipping fees when applicable, traffic direction, hours of operation, and any necessary rules and procedures.
- The site will be equipped with fire prevention equipment (fire extinguishers), spill response equipment, adequate lighting, secure fencing, and other safety measures as seen fit.
- The site will also have a trailer shelter for the site attendant equipped with electricity.

Operations and Equipment

- The site will require a full-time attendant during operating hours. The attendant will be responsible for monitoring the gate and directing vehicles to the correct locations. The attendant will record and supervise transfer station activities.
- The site will require an equipment operator to maintain the aesthetics of the transfer station, move waste as necessary, and manage snow during winter timeframes.
- Based on the findings of the SWMF Study, it is believed that Pheasant Rump Nakota Nation possesses the necessary equipment to operate the transfer station. If it is recognized that additional equipment is necessary, the client will be notified immediately.

Preliminary Design Report, Pheasant Rump Nakota Nation Transfer Station

Date: 17 August 2021 Page | 7

PROJECT UPDATE

A site has been selected for the primary transfer station and approved by the PMT. The geotechnical investigation, topographical survey, site familiarization, and desktop reconnaissance for the site have been completed. The preliminary design has been submitted here within.

Conceptual drawings of all 3 discussed options are provided in Appendix A. Option 1 was the preferred choice based on our initial meeting; therefore, additional drawings have been provided for option 1 in Appendix B.

PINTER has and will continue to supply the necessary resources to ensure the project is still completed within the fiscal year. A new project schedule has been developed with tasks being fast-tracked or completed simultaneously when possible. An updated project schedule is provided in Appendix C.

A design package including tender documents and specifications will be prepared immediately following approval of the conceptual design.

Date: 17 August 2021

CLOSURE

Please contact PINTER at (306) 244-1710 if there are any questions or comments related to this Preliminary Design Report. This document summarizes the Pheasant Rump Waste Transfer Station Design Guidelines. By signing below, the Client and the Consultant agree to the design guidelines as described in this document.

Consultant's Signature

Bennet Awume, M.Sc., P. Eng.

Project Engineer

Client's Signature

Darren Svedahl, on behalf of Pheasant Rump Chief and Council Project Manager

ATTACHMENTS


Appendix A – Conceptual Drawings

Appendix B – Option 1 Preliminary Drawings

Appendix C – Updated Schedule


Appendix D – Class C Cost Estimate

file: H:\2) Projects\2782 Pheasant Rump Transfer Station Design and Construction\2782-1 Pre-Design Phase\Preliminary Design Report\2782 Preliminary Design Draft Report-17Aug21.docx












SITE LOCATION

ISSUED FOR REVIEW



LIST OF PROJECT DRAW	/INGS
NAME OF DRAWINGS	FIGURE NO.
SECTION COVER	000
SITE LOCATION	S-1





GENERAL LAYOUT


ISSUED FOR REVIEW



LIST OF PROJECT DRAWINGS	
NAME OF DRAWINGS	FIGURE NO.
SECTION COVER	000
OVERALL SITE LAYOUT	GL-1
TOPOGRAPHIC LAYOUT	GL-2
PROPOSED SITE CROSS SECTIONS	GL-3









710A-48TH STREET EAST SASKATOON SK S7K 5B4 TREATY 6 TERRITORY, CANADA 306.244.1710 pintermain@pinter.ca

NOTES:

- THIS DRAWING IS PREPARED FOR ILLUSTRATIVE PURPOSES ONLY.
- 2. THIS IS NOT A LEGAL SURVEY.
- 3. ALL MEASUREMENTS ARE IN METRES.

			LEGEND
ISSUED FOR REVIEW	04 AUGUST 2021	BENNET AWUME	
PLAN DESCRIPTION / REVISION	DATE	BY	

PROPOSED SITE CROSS SECTIONS DATE: 04 AUGUST 2021 FILENAME:

	2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.
SCALE: N.T.S	DRAWN BY: NA, TL
FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION DESIGN & CONSTRUCTION\2782 DRAWINGS	CHECKED BY: BA, PZ


RETAINING WALLS

ISSUED FOR REVIEW



LIST OF PROJECT DRAWIN	IGS
NAME OF DRAWINGS	FIGURE NO.
RETAINING WALL — LOCATIONS	RW-0
RETAINING WALL LAYOUT	RW-1
RETAINING WALL - SECTION & DETAILS	RW-2
TIRE RECYCLING AREA DETAILS	RW-3







RETAINING WALL SECTION & DETAILS

2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.


05 AUGUST 2021

DRAWN BY: TL

CHECKED BY: KM, PZ

SCALE: 1: 20

FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION DESIGN & CONSTRUCTION\2782 DRAWINGS



12 AUGUST 2021

5 AUGUST 2021

DATE

THOMAS LI

PETER ZRYMIAK

BY

2 ADJUST DRAWING SCALE

PLAN DESCRIPTION / REVISION

ISSUED FOR REVIEW

NOTES:

PURPOSES ONLY.

2. THIS IS NOT A LEGAL SURVEY.

THIS DRAWING IS PREPARED FOR ILLUSTRATIVE

3. THE DRAWING SCALE IS BASED ON 36 X 24 INCHES

PAPER SIZE. ALL MEASUREMENTS ARE IN METRES.

PINTER

& ASSOCIATES LTD

710A-48TH STREET EAST

SASKATOON SK S7K 5B4

TREATY 6 TERRITORY, CANADA 306.244.1710


pintermain@pinter.ca



750mm WIDE x 750mm HIGH x 1500mm LONG INTERLOCKING CONC BLOCKS (MAX 2 BLOCKS HIGH), SEE OCTA-BLOC DETAIL

6.75m 6.00m 13.50m ALTERNATE COURSES OF THE CONC BLOCKS SHALL BE OFFSET BY $\frac{1}{2}$ A BLOCK WIDTH. $\frac{1}{2}$ SIZED BLOCKS SHALL BE USED IN ALTERNATE LAYERS AT THE ENDS TO CREATE AN EVEN EDGE.


GRAVEL WITH
SLOPED 1% AWAY
FROM RETAINING
WALL



OCTA-BLOC DETAIL OR EQUIVALENT

TIRE RECYCLING AREA

BLOCK COUNT: 59 1/2 BLOCK COUNT: 6



CROSS SECTION A-A'
Escale: 1:20



SASKATOON SK S7K 5B4

TREATY 6 TERRITORY, CANADA

306.244.1710

pintermain@pinter.ca

NOTES:

THIS DRAWING IS PREPARED FOR ILLUSTRATIVE PURPOSES ONLY.

2. THIS IS NOT A LEGAL SURVEY.

3. THE DRAWING SCALE IS BASED ON 36 X 24 INCHES PAPER SIZE. ALL MEASUREMENTS ARE IN METRES.

				LEGEND
2	ADJUST DRAWING SCALE	12 AUGUST 2021	THOMAS LI	
1	ISSUED FOR REVIEW	05 AUGUST 2021	PETER ZRYMIAK	
	PLAN DESCRIPTION / REVISION	DATE	BY	

RW-3

TIRE RECYCLING AREA DETAILS

05 AUGUST 2021 FILENAME:

2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.

SCALE: 1: 125

FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION
DESIGN & CONSTRUCTION\2782 DRAWINGS
CH

DRAWN BY: TL

CHECKED BY:


CHECKED BY: KM, PZ


ROAD & GRADING

ISSUED FOR REVIEW





LIST OF PROJECT DRAWINGS		
NAME OF DRAWINGS	FIGURE NO.	
SECTION COVER	000	
ROAD & GRADING — LOCATIONS	R-1	
TYPICAL ROAD CROSS SECTION	R-2	





ROAD CROSS SECTION A-A'





ROAD & GRADING LOCATIONS

ROAD CROSS SECTION B-B'



710A-48TH STREET EAST SASKATOON SK S7K 5B4 TREATY 6 TERRITORY, CANADA 306.244.1710 pintermain@pinter.ca

NOTES:

- THIS DRAWING IS PREPARED FOR ILLUSTRATIVE

 BURDOSES ONLY
- 2. THIS IS NOT A LEGAL SURVEY.
- 3. ALL MEASUREMENTS ARE IN METRES.

ISSUED FOR REVIEW 06 AUGUST 2021 BENNET	ΓAWUME
PLAN DESCRIPTION / REVISION DATE B'	Y

ASSUMPTIONS

AVERAGE DAILY TRAFFIC (ADT): 360

AVERAGE DAILY TRUCK TRAFFIC (ADTT): 18

CBR OF SUBGRADE: 20

BASE MATERIAL: SANDY GRAVEL
SUB-BASE MATERIAL: SILTY CLAY

TYPICAL ROAD CROSS SECTION

DATE:

06 AUGUST 2021
FILENAME:

2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.

DRAWN BY:

DRAWN

NOT TO SCALE

FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION
DESIGN & CONSTRUCTION\2782 DRAWINGS

()


DRAWN BY:
DRAWN BY:
CHECKED BY:
CHECKED BY: BA, PZ


BARRIERS

ISSUED FOR REVIEW



LIST OF PROJECT DRAWINGS		
NAME OF DRAWINGS	FIGURE	NO.
SECTION COVER	000	
BARRIERS & SECURITY	B-1	
FENCE DETAILS	B-2	
PARKING STOP & BOLLARD DETAILS	B-3	
HAND & GUARD RAILS DETAIL	B-4	






1. Gate and end posts shall be lengthened when


arms are used.


shown.


barbed wire is specified, except when barbed wire


A. All dimensions are in millimetres unless otherwise











CORNER AND STRAINING POST WITH BARBED WIRE ARM

FENCE, CHAIN LINK

INSTALLATION - ROADWAY

LINE POST WITH BARBED WIRE ARM

FENCE, CHAIN LINK
COMPONENT - BARBED WIRE

<u>LEGEND</u> B-2 NOTE: PINTER & ASSOCIATES LTD THE DRAWING SCALE BASED ON 34" x 22" PAPER SIZE. FENCE & GATE DETAILS 05 AUGUST 2021 2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK 710A-48TH STREET EAST SASKATOON SK S7K 5B4 ISSUED FOR REVIEW 05 AUGUST 2021 PETER ZRYMIAK NOT TO SCALE DRAWN BY: NA 306.244.1710 pintermain@pinter.ca PLAN DESCRIPTION / REVISION DATE BY FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION CHECKED BY: BA, PZ DESIGN & CONSTRUCTION\2782 DRAWINGS

End, corner, or


straining post


88.9

2.9

2.3

114.3





PARKING STOP SECTION

DATE

BY

NOTES:

A. Class of concrete shall be C2 according to CSA A23.1.

B. All dimensions are in millimetres unless otherwise shown.


PINTER 710A-48TH STREET EAST SASKATOON SK S7K 5B4

306.244.1710 pintermain@pinter.ca

<u>LEGEND</u> NOTE: THE DRAWING SCALE BASED ON 34" x 22" PAPER SIZE. ISSUED FOR REVIEW 05 AUGUST 2021 PETER ZRYMIAK

PLAN DESCRIPTION / REVISION

BOLLARD DETAIL



NOTES:

- 1. FOR INTERIOR APPLICATIONS USE ASTM-A53 PIPE DN150 STD. WEIGHT (168mm O.D. x 7.11mm THICK WALLS, YEILD STRENGTH 205 MPa MINIMUM) FOR EXTERIOR APPLICATIONS USE ASTM-A53 PIPE DN200 STD. WEIGHT (219mm O.D. x 8.18mm THICK WALLS, YIELD STRENGTH 205 MPa MINIMUM)
- 2. CONCRETE FOR FOUNDATIONS AND FILLING OF TUBE, TO BE C-2 EXPOSURE CLASS, 32 MPa MINIMUM STRENGTH AT 28 DAYS. 5 - 8% AIR ENTRAINMENT. MEET SULPHATE RESISTANCE EXPOSURE CLASSIFICATION WHEN SPECIFIED ELSEWHERE IN THE DRAWINGS OR SPECIFICATIONS. VIBRATE AND CONSOLIDATE CONCRETE IN PLACE.
- 3. HOT DIP GALVINIZE PIPE AFTER SECTIONS HAVE BEEN CUT TO LENGTH, AS PER CAN/CSA G164-M92 (R2003), MINIMUM 610 G/SQUARE METRE OF ZINC
- FOR ADDIATIONAL FINISHES REFER TO ARCHITECTURAL DRAWINGS SPECIFIC TO PROJECT. PRIME AND FINISH PAINT YELLOW.
- 4. DESIGN LOADS:

NBC 2010/2015/OBC 2012 - VEHICLE GUARD RAILS CLAUSE 4.1.5.15 LOAD = 22 kN.

5 TONNE FORKLIFT IMPACT @ 20% OF TOTAL MASS = 20 kN.

CHBDC, CSA S6-14, TL-1 VEHICULAR COLLISION LOAD = 25 kN. LOADS APPLIED @ 500mm ABOVE GROUND SURFACE

- 5. LATERAL DESIGN SOIL PRESSURE 65 kPa. FOR SERVICE IMPACT UNDER VEHICLE COLLISION LOAD (25 kN) SOME BOLLARDOUT OF PLUMBNESS MAY BE NOTICED DUE TO SOIL MOVEMENT. BOLLARD MAY REQUIRE REPLACEMENT AFTER SUCH OCCURANCES.
- 6. AT DOOR OPENING, SET INSIDE FACE OF BOLLARD @ 25mm (1") INSIDE OF CLEAR DOOR OPENING WIDTH TO PROTECT DOOR JAMB.
- 7. SUPPLY AND INSTALL HIGH DENSITY POLYETHYLENE UV RESISTANT BOLLARD SLEEVES (POST GUARD) ON ALL BOLLARDS. EACH SLEEVE TO BE YELLOW AND HAVE TWO REFLECTIVE STRIPES (RED). CONTRACTOR TO COORDINATE SIZING WITH BOLLARD SIZE. SLEEVE TO BE FASTENED (STAINLESS STEEL SCREWS)
- * TO GALVINIZED PIPE AT BOTTOM.

B-3

PARKING STOP & BOLLARD DETAIL

05 AUGUST 2021


2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.

NOT TO SCALE FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION

DESIGN & CONSTRUCTION\2782 DRAWINGS

CHECKED BY: BA, PZ


DRAWN BY: NA





HAZARDOUS WASTE BUILDING ISSUED FOR REVIEW



LIST OF PROJECT DRAWINGS		
NAME OF DRAWINGS	FIGURE NO.	
SECTION COVER	000	
HAZARDOUS WASTE BUILDING DESIGN	HW-1	
HAZARDOUS WASTE BUILDING DETAILS	HW-2	









2 SECTION AT LATERAL WALL BRACING


1 BUILDING SECTION







ISSUED FOR REVIEW

PLAN DESCRIPTION / REVISION





38x140 @ 300 C/C LOOKOUT RAFTERS









05 AUGUST 2021






TYPICAL HOUSEKEEPING PAD

PINTER & ASSOCIATES LTD	
	d Absociat Es Li D

710A-48TH STREET EAST SASKATOON SK S7K 5B4 TREATY 6 TERRITORY, CANADA 306.244.1710 pintermain@pinter.ca

NOTES:

- 1. THE DRAWING SCALE BASED ON 34" x 22" PAPER SIZE.
- 2. THIS DRAWING IS PREPARED FOR ILLUSTRATIVE PURPOSES ONLY.
- 3. THIS IS NOT A LEGAL SURVEY.
- 4. ALL MEASUREMENTS ARE IN METRES.



	HW-2 HAZARDOUS WASTE BUILDING DETAILS
	DATE: 05 AUGUST 2021 FILENAME: 2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.
SCALE: 1: 50	DRAWN BY: NA
FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION DESIGN & CONSTRUCTION\2782 DRAWINGS	CHECKED BY: BA, PZ

SURFACE WATER DRAINAGE ISSUED FOR REVIEW




LIST OF PROJECT DRAWINGS										
NAME OF DRAWINGS	FIGURE NO.									
SECTION COVER	000									
SURFACE WATER DRAINAGE	SW-1									



UTILITIES ISSUED FOR REVIEW



LIST OF PROJECT DRAWINGS									
NAME OF DRAWINGS	FIGURE NO.								
SECTION COVER	000								
UTILITIES PLAN	U-1								



BINS ISSUED FOR REVIEW



LIST OF PROJECT DRAWINGS										
NAME OF DRAWINGS	FIGURE NO.									
SECTION COVER	000									
BIN DETAILS	BIN-1									





710A-48TH STREET EAST SASKATOON SK S7K 5B4 306.244.1710 pintermain@pinter.ca

NOTE:

THIS DRAWING IS PREPARED FOR ILLUSTRATIVE PURPOSES ONLY.

PETER ZRYMIAK ISSUED FOR REVIEW 06 AUGUST 2021 PLAN DESCRIPTION / REVISION DATE BY

<u>LEGEND</u>

NOT TO SCALE

FILE: H:\2) PROJECTS\2782 PHEASANT RUMP TRANSFER STATION DESIGN & CONSTRUCTION\2782 DRAWINGS


06 AUGUST 2021

BIN DETAILS

2782 TRANSFER STATION DESIGN & CONSTRUCTION, PHEASANT RUMP, SK.

DRAWN BY: NA


CHECKED BY: BA, PZ





UPDATED SCHEDULE - ENGINEERING SERVICES FOR SOLID WASTE TRANSFER STATION DESIGN AND CONSTRUCTION, PRNN, SK

		May-21				21			Jun-21		Jul-21			Aug-21				Sep-21				Oct-21				Nov-21				
Detailed Project Schedule	Main Task Duration (Weeks)	3	10	17	24	31	7	14	21	28	5	12	19	26	2	9 :	.6 2	3 30	6	13	20	27	4	11	18 2	25	2 9	16	23	30
Project Awarded																														
Project Management	23																													
Ongoing project management	25																													
Cost and schedule control																														
Assessment/PreDesign Phase																														
Attend Project Initiation Meeting																												<u> </u>		
Review existing technical and other available documents																														
Conduct site inspections/evaluation	4																													
Complete detailed site investigation for new facility	, 																													
Prepare pre-design drawings and Class C construction cost estimate for each design option																														
Attend a meeting with PMT to discuss findings and obtain approval for recommended option																														
Prepare final pre-design report																														
Pre-design report approval																														
Design Phase																														
Prepare 33% design drawings]																													$oxed{oxed}$
Present Class B construction cost estimate for the design at 50% design meeting	4																													
Present 90% design drawing and specifications																												\perp	\perp	
Prepare 99% design drawings for review																														
Final design report and Class A construction cost estimate																												Ш.		
Tender Phase																														
Prepare tender advertisement, pre-tender estimates and the conditions for the project	5																													
Facilitate tendering process (including pre-bid meeting)																														
Contract administration																														
Construction Phase																														
Pre-construction kick-off meeting																												\top	\top	
Construction management (including project close-out meeting) - 4 days on-site	9								1										1										1	1
Construction QA/QC field services - 4 days on-site																													1	
On-site records								1	1										1										1	1
Post-Construction Phase																														
Record drawings	4								T																					T
Final inspection after warranty period (including travel) - September 2022																1			1											1
Recommendations for Certificate of Completion - September 2022									1							1			1				1					1	\top	1



2782 - PRNN Transfer Station Capital Cost Estimate Option 1

Item#	Line Item Name	Quantity	Unit	Į	Jnit Price		Amount
1	Mobilization/Demobilization	1	Unit	\$	20,000.00	\$	20,000
2	Topsoil Stripping/Stockpiling	3,080	m ³	\$	5.00	\$	15,400
3	Site Grading (Cut)	13,300	m ³	\$	6.00	\$	79,800
4	Site Grading (Fill)	2,000	m ³	\$	6.50	\$	13,000
5	Roadway Subgrade Preparation	4,300	m ²	\$	4.00	\$	17,200
6	Roadway Surfacing	4,300	m ²	\$	4.00	\$	17,200
7	Bin Pads	200	m ²	\$	4.00	\$	800
8	Aggregate Supply	2,500	tonnes	\$	45.00	\$	112,500
9	Retaining Walls	60	m	\$	2,500.00	\$	150,000
10	Hazardous Waste Building	1	LS	\$	100,000.00	\$	100,000
11	Culverts	40	m	\$	300.00	\$	12,000
12	Fencing	400	m	\$	50.00	\$	20,000
13	Topsoil Placement/Seeding	2,600	m ²	\$	2.50	\$	6,500
14	6 yd Bins	6	Each	\$	2,500.00	\$	15,000
15	30 yd Bins	1	Each	\$	9,500.00	\$	9,500
16	HW Storage Containers	1	LS	\$	12,000.00	\$	12,000
17	Security system	1	LS	\$	20,000.00	\$	20,000
18	Lighting	1	LS	\$	15,000.00	\$	15,000
19	Power to site	1	LS	\$	70,000.00	\$	70,000
20	Attendants shack	1	LS	\$	30,000.00	\$	30,000
21	Gate	1	LS	\$	20,000.00	\$	20,000
22	Signs	1	LS	\$	15,000.00	\$	15,000
23	Litter fencing	1	LS	\$	20,000.00	\$	20,000
			_	700.000			
- 25	I	4.5			Subtotal	\$	790,900
25	Contingency	15	%	\$	118,635		
					Subtotal TOTAL	\$	118,635
				\$	909,535		

2782 - PRNN Transfer Station Capital Cost Estimate Option 2

Item #	Line Item Name	Quantity	Unit	Ţ	Jnit Price	Amount
1	Mobilization/Demobilization	1	Unit	\$	20,000.00	\$ 20,000
2	Topsoil Stripping/Stockpiling	3,080	m ³	\$	5.00	\$ 15,400
3	Site Grading (Cut)	13,300	m ³	\$	6.00	\$ 79,800
4	Site Grading (Fill)	2,000	m ³	\$	6.50	\$ 13,000
5	Roadway Subgrade Preparation	4,300	m ²	\$	4.00	\$ 17,200
6	Roadway Surfacing	4,300	m ²	\$	4.00	\$ 17,200
7	Bin Pads	200	m ²	\$	4.00	\$ 800
8	Aggregate Supply	2,500	tonnes	\$	45.00	\$ 112,500
9	Retaining Walls	60	m	\$	2,500.00	\$ 150,000
10	Hazardous Waste Building	1	LS	\$	100,000.00	\$ 100,000
11	Culverts	40	m	\$	300.00	\$ 12,000
12	Fencing	400	m	\$	50.00	\$ 20,000
13	Topsoil Placement/Seeding	2,600	m ²	\$	2.50	\$ 6,500
14	6 yd Bins	2	Each	\$	2,500.00	\$ 5,000
15	20 yd Bins	2	Each	\$	8,500.00	\$ 17,000
16	30 yd Bins	1	Each	\$	9,500.00	\$ 9,500
17	HW Storage Containers	1	LS	\$	12,000.00	\$ 12,000
18	Security system	1	LS	\$	20,000.00	\$ 20,000
19	Lighting	1	LS	\$	15,000.00	\$ 15,000
20	Power to site	1	LS	\$	70,000.00	\$ 70,000
21	Attendants shack	1	LS	\$	30,000.00	\$ 30,000
22	Gate	1	LS	\$	20,000.00	\$ 20,000
23	Signs	1	LS	\$	15,000.00	\$ 15,000
24	Litter fencing	1	LS	\$	20,000.00	\$ 20,000
			_		Subtotal	\$ 797,900
25	Contingency	15	%			\$ 119,685
	\$ 119,685					
					TOTAL	\$ 917,585

2782 - PRNN Transfer Station Capital Cost Estimate Option 3

Item#	Line Item Name	Quantity	Unit	Į	Jnit Price	Amount
1	Mobilization/Demobilization	1	Unit	\$	20,000.00	\$ 20,000
2	Topsoil Stripping/Stockpiling	3,080	m ³	\$	5.00	\$ 15,400
3	Site Grading (Cut)	13,300	m ³	\$	6.00	\$ 79,800
4	Site Grading (Fill)	2,000	m ³	\$	6.50	\$ 13,000
5	Roadway Subgrade Preparation	4,300	m ²	\$	4.00	\$ 17,200
6	Roadway Surfacing	4,300	m ²	\$	4.00	\$ 17,200
7	Bin Pads	200	m ²	\$	4.00	\$ 800
8	Aggregate Supply	2,500	tonnes	\$	45.00	\$ 112,500
9	Retaining Walls	60	m	\$	2,500.00	\$ 150,000
10	Hazardous Waste Building	1	LS	\$	100,000.00	\$ 100,000
11	Culverts	40	m	\$	300.00	\$ 12,000
12	Fencing	400	m	\$	50.00	\$ 20,000
12	Topsoil Placement/Seeding	2,600	m ²	\$	2.50	\$ 6,500
12	6 yd Bins	6	Each	\$	2,500.00	\$ 15,000
15	20 yd Bins	2	Each	\$	2,800.00	\$ 5,600
16	Equipment Storage Building	1	LS	\$	650,000.00	\$ 650,000
17	HW Storage Containers	1	LS	\$	12,000.00	\$ 12,000
18	Security system	1	LS	\$	20,000.00	\$ 20,000
19	Lighting	1	LS	\$	15,000.00	\$ 15,000
20	Power to site	1	LS	\$	70,000.00	\$ 70,000
21	Attendants shack	1	LS	\$	30,000.00	\$ 30,000
22	Gate	1	LS	\$	20,000.00	\$ 20,000
23	Signs	1	LS	\$	15,000.00	\$ 15,000
24	Litter fencing	1	LS	\$	20,000.00	\$ 20,000
			_		Subtotal	\$ 1,382,000
25	Contingency	15	%			\$ 207,300
					Subtotal	\$ 207,300
					TOTAL	\$ 1,644,300